NectarCAM - Camera Mechanical Structure Status





Ouline

CDMR RIXes

- Status of NectarCAM 1 (QM)
- Production of Camera Structures

- Feedback on call for tender procedure
- Final remarks / conclusion



Mechanical System CDMR RIXes

High priority - closed

- Camera mass: agreement of MST Structure to increase limit to 2.5 tons
 - Mass of QM is around 2.3 T, targeting < 2.2 T for production cameras
- Wind resistance of window blind: agreement of CTAO to accept ISO standard as reference document, commercial product meeting standard found by LP2iB

Several low priority still opened - on hold

- Feedback to comments on CDMR documents: mostly done
- Couple of requests related to the window blind: will need some work
- Incomplete or missing maintenance documentation: major task to write the maintenance manuals, which concerns not only the Mechanical Work package.
- Closure of the RIXes: currently not the priority for Mech. WP.



NectarCAM 1 (QM) Status

- Still a couple of missing components but non critical for the qualification and test of the camera
- Window is installed but without its blind
- Right PSB mechanical box has to be replaced
 - Designed updated to solve an interference problem with the Backplane Ethernet cables
 - Currently waiting for quotation from manufacturer
- A couple of small mechanical supports for new devices (power switches, network separators) are missing
 - Procurement is ongoing
- Dry air circuit is missing
 - Procurement of the needed component has been done (valve, fittings...)
 - Installation is quick and simple with no impact on the other components




Production of Camera Structures

- One contract for the delivery of fully assembled Main Camera Structures with embedded cooling system
 - Contract managed by LLR
 - Fabrication, mechanical assembly and tests performed by the contractor
 - All the procurements managed by the contractor, except heat exchangers and cooling system sensors
- One contract for the production of the camera windows
 - Contract managed by LP2iB
 - Some assembly work and tests done by LP2iB
 - Some procurements managed by LP2iB
- Other mechanical items: small mechanical parts and supports, fasteners for Nectar Modules and Backplanes...
 - TBD, probably a couple of different procurements
 - Collaboration between LLR and IRFU AIV team to manage them



Production of Main Camera Structures





Main Camera Structures

- Call for tender done, contract awarded to Spanish company RAMEM/ARQUIMEA
 - Same company that produced the LST cameras
 - Extensive expertise in manufacturing similar assemblies
 - Best offer in terms of price
- Contract passed for the delivery of 4 Camera Structures with embedded cooling system
- Contract includes option for 1 to 4 additional Camera Structures (request from project NectarCAM project management)
- Delivery of one Camera Structure every 4 months
- Cost is around 12% above latest cost estimate (8% above for additional Camera Structures)



Camera Structure Production

Delivery schedule (prepared by RAMEM)

NCAM 2: March 2023

NCAM 5: March 2024


NCAM 6: July 2024

• NCAM 9: July 2025

0	Contract Kick-off Meeting
1	PA docs Review
2	MRR Manufacturing Readiness Review
3	Completion of Machining
4	Completion of Welding
5	Completion of Main Assemblies
6	TRR Integration & Test Readiness Review
7	Start of the Assembling/Integration
8	Functional Tests Review
9	Final Acceptance & Handover

NATURE OF WORKS
Engineering & Mngt
Operations
Test Execution
Quality Assurance

EARQUIMEA





Feedback on call for tender procedure

- Oct 28th 2021 First contact with regional CNRS Contracts and Procurements Office
- Jan 14th 2022 First release of specification document delivered to CNRS
- April 12th 2022 Final versions of all the documents available (technical and administrative)
 - Many iterations to agree on criteria for tender acceptance and tender evaluation
- April 19th 2022 Call for tender was officially published
- June 7th 2022 Due date for the bids (3 received)
 - Several iterations to finalize the analysis report of the bids
- July 5th 2022 contract was officially awarded to RAMEM/ARQUIMEA
- August 3rd 2022 Kick-off meeting with RAMEM



Conclusion

- The production of the camera mechanical structures is on track for a delivery of the structures to AIV with a rate of 3 per year as expected
 - The contract is passed for 4 structures only. Official decision for the 4 other ones has to be given at the latest early next year (official chain of decision?)
- The collaboration with RAMEM company is efficient thanks to the experience and expertise of the engineers in charge of the project.
- Preparing the fabrication of the first structure is still very time consuming: many request from the company, updates of drawings...
- Expecting to have some spare time to deal with other activities such as RIXes and maintenance documentation from early next year